

DOCUMENT 00910 - ADDENDUM NO. 3

Project Title: Phase I Site Grading

Date: November 6, 2018

Client: Prairie Island Indian Community

BMI Project No.: C15.115757

Bid Date: November 7, 2018 **Bid Time:** 10:00 a.m.

QuestCDN No.: 5720729

1.1 **GENERAL:**

A. The following changes are, by the issuance of this Addendum, made a part of the Contract Documents for the project referenced above, as if originally contained therein. Execution of the acknowledgment on the bid form shall be the bidder's acceptance of the conditions set forth herein.

1.2 **ACKNOWLEDGMENT:**

A. This addendum shall be acknowledged on the submitted bid form. Failure to do so may result in the rejection of the bid.

1.3 **PROJECT MANUAL:**

A. Section 00410 – Bid Form

1. Replace current form with Revised (See attached).

(a) Line No. 10 4' DIA. STORM SEWER MANHOLE – the Approx. Quant. has been revised to 3 EA.

(b) Line No. 23 LOW MAINT. FESCUE GRASS – the Approx. Quant. has been revised back to 9,590 LB.

(c) Add Line No. 24 4' DIA. OUTLET CONTROL STRUCTURE – Approx. Quant. is 3 EA.

B. Section 02630 – Pipe Sewers – Storm

1. Replace page 02630-1 with the revised page (See attached).


1.4 **ATTACHMENTS**

A. Bid Form REVISED_ADD3

B. Page 02630-1

1.5 **CERTIFICATION:**

I hereby certify that this addendum was prepared by me or under my direct supervision, and that I am a duly Licensed Professional Engineer under the laws of the State of Minnesota.

By:  _____

Cristina Mlejnek, P.E.
License No: 48340

****END OF ADDENDUM****

SCHEDULE OF UNIT PRICES (REVISED 11/6/18)

PHASE I SITE GRADING
 PRAIRIE ISLAND INDIAN COMMUNITY
 BMI PROJECT NO. C15.115757

BIDDER agrees to perform all of the work described in the CONTRACT DOCUMENTS for the following unit prices:

NOTE: BIDS shall include sales tax and all applicable taxes and fees.

BIDDER must fill in unit prices in numerals, make extension for each item, and total.

CY (LV) = Cubic Yards, Loose Volume

CY (CV) = Cubic Yards, Compacted Volume (Measured in Place)

(P)=Planned Quantity Basis of Measurement

ITEM NO.	ITEM	APPROX. QUANT.	UNIT	UNIT PRICE	AMOUNT
BASE BID:					
1	MOBILIZATION	1	LS	_____	_____
2	TRAFFIC CONTROL	1	LS	_____	_____
3	CONSTRUCTION ENTRANCE	180	CY	_____	_____
4	BIOROLLS	128	LF	_____	_____
5	SILT FENCE TYPE MACHINE SLICED	12770	LF	_____	_____
6	DEBRIS REMOVAL	1	ALLOWANCE	\$0.01	\$0.01
7	COMMON EXCAVATION (EV) (P)	131652	CY	_____	_____
8	SUBGRADE EXCAVATION (EV)	10000	CY	_____	_____
9	ONSITE BORROW EXCAVATION (EV) (BACKFILL FROM MINED AREA)	1900	CY	_____	_____
10	4' DIA. STORM SEWER MANHOLE	3	EA	_____	_____
11	12" RCP STORM PIPE, CLASS	232	LF	_____	_____
12	18" RCP STORM PIPE, CLASS	341	LF	_____	_____
13	21" RCP STORM PIPE, CLASS	914	LF	_____	_____
14	12" RCP FLARED END SECTION	3	EA	_____	_____
15	18" RCP FLARED END SECTION	2	EA	_____	_____
16	21" RCP FLARED END SECTION	2	EA	_____	_____
17	STORM DRAIN INLET PROTECTION	1	EA	_____	_____
18	CLASS III RIP RAP	52	CY	_____	_____
19	FERTILIZER 10 - 20 - 20	8920	LB	_____	_____
20	SEEDING	44.6	AC	_____	_____
21	DISC ANCHORED MULCH, TYPE I	44.6	AC	_____	_____
22	EROSION CONTROL BLANKET, CAT 3	13410	SY	_____	_____
23	LOW MAINT. FESCUE GRASS - PRAIRIE MOON NURSERY ECO-GRASS M	9590	LB	_____	_____
24	RIPARIAN SOUTH AND WEST MnDOT MIX 34-261	32.9	LB	_____	_____
25	4' DIA. OUTLET CONTROL STRUCTURE	3	EA	_____	_____
TOTAL BASE BID:					=====

SECTION 02630 - PIPE SEWERS - STORM

PART 1 -- GENERAL

1.1 SUMMARY

- A. This section covers the furnishing of all labor, materials, tools, equipment and performances of all work and services necessary or incidental to storm sewer construction as indicated on the drawings or as specified herein.

1.2 METHOD OF MEASUREMENT AND PAYMENT

- A. Measurement and compensation for the following items shall be paid according to the referenced specification or as modified below:

1. Manholes/Structures

- (a) Payment for all manholes *and outlet control structures* shall be at the unit price bid per EACH (EA) of structure. The amount bid includes all work and material required to complete the structure. Casting assemblies shall be *incidental to this bid item*.

2. Catch Basins

- (a) Payment for all catch basins shall be at the unit price bid per EACH (EA) of structure. The amount bid includes all work and material required to complete the structure. Casting assemblies shall be *incidental to this bid item*.

3. Casting Assemblies

- (a) Incidental

4. Sewer Pipe

- (a) RCP Storm sewer pipe shall be measured and paid by LINEAL FOOT (FT) for each diameter and class installed.

- (b) No exception to the referenced specification is made.

5. Aprons

- (a) RCP Flared End Sections shall be measured and paid by EACH (EA) for each size installed.

- (b) No exception to the referenced specification is made.

- B. The furnishing and installing of specific items and/or the performance of work under certain circumstances shall not be individually paid in the absence of a specific bid item for the work. The costs shall be included in the unit price bid for the storm sewer items, as indicated. Such items of work include but are not limited to:

1. Locating and connecting to an existing storm sewer, include in the price bid for storm sewer.
2. The costs of furnishing bends, adapters, cutting and removing the existing storm sewer pipe, include in the price bid for storm sewer.
3. Locating and connecting to an existing storm sewer service laterals, include in the price bid for service connections.
4. Use of geotextile fabric to wrap pipe joints in lieu of using mastic, include in the price bid for storm sewer.
5. Maintenance of an appropriate storm water outlet during construction, include in the price bid for storm sewer.
6. The cost of all labor, equipment and materials necessary for testing of storm sewer, if required, included in the price bid for storm sewer.